



# Fiscal Year 2018 (FY18) Rio Grande Valley (RGV) Levee/Border Wall System Construction Projects Overview

The wall system will be similar to other levee and border wall system infrastructure located within the RGV Sector. In this handout, you will find maps showing the locations for levee wall system in Hidalgo County and border wall system in Starr County. The approximate mileage is as follows:

## Hidalgo County

APPROXIMATELY

**25**  
Miles

## Starr County

APPROXIMATELY

**8-12**  
Miles

Regarding the approximate 25 miles of levee wall system in Hidalgo County, the proposed alignment would be situated on the south face of the northern U.S. International Boundary Water Commission (IBWC) levee. The proposed design includes a reinforced concrete levee wall system to the approximate height of the existing levee with 18-foot tall steel bollards installed on the top of the levee wall system. The project would also include a 150-foot enforcement zone on the south/river side of the levee wall system, detection and surveillance technology that would be incorporated into the levee wall system, automated vehicle gates, pedestrian gates, an all-weather patrol road that would run parallel to the levee wall system, and enforcement zone lighting.



